The quotations should be sent so as to reach the Chief Electrical Engineer to the Government of Mysore, Bangalore, on or before 3rd December 1938, 12 noon, and the covers containing them should be marked "Quotation for fuse-wires to be opened at 12 noon on 3rd December 1938."

Withdrawal from the quotation after it is accepted or failure to make the supply within the specified time or according to specifications will entail cancellation of the order and purchases being made at your expense from other sources.

The Chief Electrical Engineer reserves to himself the right to refuse the lowest or any tender whole or part, without assigning any reason therefor.

Yours faithfully,
M. HAYATH,
For *Chief Electrical Engineer.*

OFFICE OF THE SUPERINTENDING ENGINEER.

Notification dated 7th November 1938.

Notice is hereby given that sealed tenders will be received at the Office of the Superintending Engineer, up to 3 P.M. on the 25th November 1938, for constructing Electrical Buildings at the following places. An approximate estimate of quantities is given below. These quantities are not guaranteed. The works should be completed by the 15th of March 1939.

AT T.-NARSIPUR—(MYSORE DISTRICT).

(1) Office and Stores Building.
(2) One Block of Operator's Quarters.
(3) One Block of Cooly Quarters.
(4) Two Units of Latrine.

AT GARGESWARI (T.-NARSIPUR TALUK).

(1) One Block of Cooly Quarters.

2. The plans, detailed estimate and conditions may be seen at the Office of the Superintending Engineer, Electrical Department, Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Superintending Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 400 for buildings at T.-Narsipur and Rs. 50 for building at Gargeswari in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Electrical Buildings at T.-Narsipur and Gargeswari" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason for the rejection of any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the Notice Board in the Superintending Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Public Works Department or those fixed by the Superintending Engineer, after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specially provided for and in all matters of dispute about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Superintending Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Charges on account of water, scaffolding materials implements for setting out, barricading, clearing site, supply of workmen, etc., that may be found necessary during execution will not be paid for separately, but should be borne by the contractor.

Abstract for constructing one Unit of Double Block of Operators' Quarters including one Unit of Latrine at T.-Narsipur Town.

Item No.	Description of work	Unit	Quantity	Rate to be quoted
1	Earthwork excavation and filling in basement ..	C.yd.	53	Rs. a. p.
2	Stone jelly concrete in lime mortar	C.ft.	597	
3	Size stone in clay foundation and basement with bond stones as per specification	,,	1,079	
4	Burnt brick in clay superstructure	,,	1,946	
5	Burnt brick in mortar do	,,	746	
6	Supplying and fixing burnt stone slabs 6" thick and dressed	S.ft.	249	
7	T.W. doors with battened shutters 1" thick with bolts, hinges, etc., completed, as per drawing	,,	280	
8	T.W. windows with battened shutters 1" thick with iron bar, fixture, etc., complete, as per drawing ..	,,	116	
9	Supplying and fixing T.W. shelves with two planks and shutters with locking, etc., complete	S.ft.	96	
10	T.W. wrought and put up with two coats of wood oiling.	C.ft.	51·55	
11	T.W. caveboard 9" deep including fixing	R.ft.	149	
12	Roofing with first class Mangalore Tiles on T.W. reepers 2"×1" including wood-oiling to the reepers ..	Sqr.	12·28	
13	Mangalore ridge tiles set in mortar including cement pointing	R.ft.	78	
14	Providing and fixing rolled steel joists (Tata's tested) including painting	Cwt.	6·36	
15	Boxing girders with brick in cement and plaster complete	R.ft.	20	
16	R.C. brick-nogged terrace with brick in surki mortar with wedge-shaped R.C. joists, surki concrete, two layers of flat tiles, plastered, etc., complete as per specification	Sqr.	3·74	
17	Parapet wall as per design	R.ft.	60	
18	Cornice as per design all round	,,	63	
19	Flooring with 1½" thick cement concrete, 3" lime concrete with ½" thick cement plaster on top and coloured red.	Sqr.	9·00	
20	Plastering with lime mortar two coats	Sq.	50·00	
21	Cement pointing with thread lines	,,	2·20	
22	White and colour washing, two coats	,,	52·20	
23	Rain water down pipes of 3" dia. of plain galvanised iron sheets 22 BWG-fixed with clamps, etc., complete with painting	R.ft.	65	
24	Mortar bands including plastering, etc., complete ..	,,	24	
25	Chocolate painting, two coats	Sqr.	13·33	
26	Expanded metal 3"×1½" mesh with ⅛" strand with T.W. frame including door-way complete	S.ft.	123	
27	Providing chimney, etc.	L.S.	..	
28	Constructing sinks, complete with outlet pipes ..	No.	2	
29	Providing and fixing stone-mortar pestle	,,	2	
30	Providing and fixing copper handas in bath rooms ..	,,	2	
31	Levelling ground	L.S.	..	

Abstract of the estimate of the probable cost of constructing Combined Station, Office and Stores Building at T.-Narsipur Town.

Item No.	Description of the work	Unit	Quantity	Tendered rate in	
				Figures	Words
1	Earthwork excavation and filling in basement ..	C.yd.	39		
2	Stone jelly in lime mortar concrete for foundation ..	C.ft.	361		
3	Stone in lime foundation and basement, including through stones 6 ft. apart in every course	,,	869		
4	Burnt brick in clay superstructure	,,	1,298		
5	Burnt brick in mortar superstructure	,,	144		
6	Stone slabs 6" thick roughly dressed and fixed in mortar	,,	177		

Item No.	Description of the work	Unit	Quantity	Tendered rate in	
				Figures	Words
7	Stone slabs 3" thick exposed parts one line dressed and set in mortar	S.ft.	7		
8	Brick in mortar pillars 1½ square, 9¾ ft. high including stone base and capital and cement plastering ½" thick	Each	4		
9	Chunam plastering, two coats	Sqr.	29·00		
10	Cement pointing with thread lines	,,	1·88		
11	White and colour washing, two coats	,,	31·00		
12	Brick cornice 6" projection as per design	R.ft.	158·00		
13	Brick in mortar parapet wall 9" thick, as per design ..	,,	155·00		
14	Chunam moulding in front wall between pillars as per design	No.	4		
15	Chunam moulding 6" × ½" around Ventilators ..	R.ft.	77		
16	Cement concrete flooring 1½" thick on 4" concrete bed and cement plastered ½" red coloured cement thick.	Sqr.	6·00		
17	Terrace filled with brick in surki mortar with wedge shaped R.C. joists with 3" to 6" lime concrete, two coats flat tiles surface and ceiling lime plastered ..	,,	6·75		
18	Steel work fixed complete (Tata's tested) with two coats of painting	Cwt.	8·50		
19	T.W. doors panelled 1½" thick shutters with fixtures, etc., complete as per design	S.ft.	92		
20	T.W. glazed windows 1¾" thick shutters with iron bars ⅝" dia. fixtures, etc., complete as per drawing ..	,,	70		
21	T.W. ventilators glazed with iron bars	,,	27		
22	Silicate painting, two coats	Sqr.	12·87		
23	Fixing wire-gauze shutters with T.W. battens and spring hinges complete as per drawing	S.ft.	63		
24	Rainwater down G.I. pipes fixed complete (3" dia.) including painting	R.ft.	78		
25	Brick in lime mortar and stone slabs with chunam plastering, etc., complete for brackets	No.	10		
26	Clearing site and levelling the ground	L.S.	..	Rs. 20	

Abstract of the estimate of the probable cost of constructing one block of four Linemen's Quarters at T.-Narsipur Town.

Sl. No.	Description	Unit	Quantity	Tendered rate	
				Figures	Words
1	Earthwork excavation and filling in basement including watering and ramming	C.yd.	29		
2	Concrete stone jelly in lime mortar	C.ft.	309		
3	Stone in clay foundation and basement including bond stones 6 ft. apart	,,	741		
4	Burnt brick in clay superstructure	,,	1,538		
5	Burnt brick in lime mortar superstructure	,,	537		
6	Stone slabs 4" thick roughly dressed and fixed in lime mortar	S.ft.	141		
7	Chunam plastering, 2 coats	Sqr.	44		
8	Cement pointing with thread lines	,,	1.50		
9	White and colour washing, 2 coats	,,	45.50		
10	Roofing with first class Mangalore Tiles on T.W. reepers including wood-oiling to reepers 2" × 1" ..	,,	15		
11	Ridge tiles set in mortar and cement pointed ..	R.ft.	63		
12	Ventilating tiles fixed complete	No.	16		
13	T.W. wrought and put up including wood-oiling, 2 coats	C.ft.	52.52		
14	T.W. battened doors with 1" thick shutters and all fixtures complete, as per drawing	S.ft.	156		
15	T.W. battened windows with 1" thick shutters ⅝" dia. iron bars and fixtures, etc., complete as per drawing.	,,	75		
16	T.W. cup-boards with shutters 1" thick and planks, fixtures, etc., complete with 3" × 4" frame ..	,,	60		
17	Chocolate painting 2 coats	Sqr.	5.50		

Sl. No.	Description	Unit	Quantity	Tendered rate	
				Figures	Words
18	Constructing sinks complete with out-let pipes ..	No.	4		
19	Providing and fixing stone mortar and pestle ..	"	4		
20	Flooring with 3" lime concrete 1" cement concrete and top plastered with ½" thick cement plastering ..	Sqr.	8.00		
21	Levelling the ground all round	L.S.			Rs. 10
	For Constructing Latrine.				
1	Earthwork excavation and filling in basement, complete.	C.yd.	4		
2	Burnt stone in lime mortar foundation and basement ..	C.ft.	130		
3	Burnt brick in mortar superstructure	"	193		
4	Chunam plastering, 2 coats	Sqr.	4.91		
5	Cement pointing with thread lines	"	0.56		
6	White and colour washing, 2 coats	"	5.47		
7	Cement plastering ½" thick	"	0.80		
8	Tar washing, 2 coats	"	0.63		
9	Flooring with 3" lime concrete 1" cement concrete and top finished with ½" cement plaster .. .	"	0.38		
10	Fixing outlets, constructing drains, etc.	L.S.			Rs. 10
11	Providing galvanized iron sheet tubs 12"×6" complete with tarring	No.	6		

L. A. H. WINCKLEE,
Superintending Engineer.

Notification dated 7th November 1938.

Notice is hereby given that sealed tenders will be received at the Office of the Superintending Engineer, Electrical Department, Bangalore, upto 3 P.M. on the 28th November 1938, for constructing Electrical Quarters at Hoskote and Anekal. An approximate estimate of quantities is given below. These quantities are not guaranteed. The works should be completed by the end of February 1939.

2. The plans, detailed estimate and conditions may be seen at the office of the Superintending Engineer, Electrical Department, Bangalore, between the hours 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Superintending Engineer. The tenders should be accompanied by a statement in the form given below, showing the rate at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 for buildings at Hoskote, and Rs. 100 buildings at Anekal, in cash or Government Promissory Notes, as earnest money and be superscribed "*Tender for constructing Electrical Quarters at Hoskote and Anekal,*" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Superintending Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on the rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Public Works Department or those fixed by the Superintending Engineer, after working out data with not more than 10 per cent for the Contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Superintending Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific terms of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate, will not be accepted.

13. Charges on account of water, scaffolding materials, implements for setting out, barricading, clearing site, supply of work, etc., that may be found necessary during execution, will not be paid for separately, but should be borne by the Contractor.